

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-02066-00-00
Spot: SWSENW Sec/Twnshp/Rge: 22-26S-18E
3250 feet from S Section Line, 3800 feet from E Section Line
Lease Name: CANNON A Well #: 11
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 5488
Op Name: TWM PRODUCTION CO., A GENERAL P
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	800		
SURF	10	20		

#35⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2005 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 10/28/2005 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 825'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 10" ANNULUS TO 750'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 270 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

MAR 1 2006 CPT

CHANUTE, KS

Remarks: _____

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

INVOICED

DATE

3-7-06

INV. NO

2006061232

RECEIVED

MAR 06 2006

KCC WICHITA