



18-065-20281-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
12-2-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Honas of H-30 Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Honas guarantees payment of the plugging fee.

Operator's full Name: Brandt-Clark Oil Company,

Complete Address: 505 First National Bank Building, Wichita, Kansas.

Lease Name: Goddard Well No. 1

Location: CSE-NW-SE Sec. 16 Twp. 7 Rge. (E)(W) 25

County: Graham Total Depth 3980' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Honas was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1060'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent