

State of Kansas



15-065-20097-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 23 1961
10-22-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Duane Born of Paine Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Paine Drilling Company, Incorporated,

Complete Address: Box "D", Hill City, Kansas.

Lease Name: Wilcox Well No. 2

Location: SW-SE-NW Sec. 7 Twp. 7 Rge. (E)(W) 25

County Graham Total Depth 3835' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

238'--7" OD Surface casing, cement circulated with 125 Sx. (6 1/4" hole). Dakota section from 970' to 800'.

Circulate hole with heavy mud. Pull DP to 990' and displace 55 Sx. cement thru DP. Pull DP to 270' and displace 15 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/4 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent