

State of Kansas



15-065-01058-00-00

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Rog Welty of Peel-Hardman Oil Operators has this date requested permission to plug the following described well:

Mr. Welty guarantees payment of the plugging fee.

Operator's full Name: Peel-Hardman Oil Operators.

Complete Address: Rt. #3 Box #144B, Wichita, Kansas.

Lease Name: Shughart Well No. 1

Location: NE-NE-SW Sec. 6 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3897 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Welty was instructed to plug the well as follows:

310'--8 5/8" Surface casing, cement circulated with 220 Sx.

Circulate hole with heavy mud, set plug @ 540' with 20 Sx. cement.

" " 300' with 1/4 sack hulls & 20 Sx. cement.

" " 40' with 1/2 sack hulls & 10 Sx. cement.

Very truly yours,

R. D. Nichols