

State of Kansas



15-045-20043-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 21 1967  
7-21-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drlg. Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Company,

Complete Address: 1016 Union Center, Wichita, Kansas.

Lease Name: Toll Well No. 1

Location: SW-SE-SE Sec. 15 Twp. 7 Rge. (E)(W) 25

County Graham Total Depth 3732 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

263' -- 7" OD Surface pipe, cement circulated with 150 Sx. (6 1/4 hole). Dakota section from 1788' to 1970'.

Circulate hole with heavy mud. Pull DP. to 1990' and displace hole with 60 Sx. cement to 1645' thru DP. Pull DP. to 275' and displace 15 Sx. cement thru DP. Pull DP., set plug @ 40' and 8 Sx. cement to bottom of cellar.

Very truly yours,

H. S. Nichols  
Conservation Division Agent