



15-065-01310-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas
12-8-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Glen W. Peel,

Complete Address: R. R. #3, Box #1114-B Wichita, Kansas.

Lease Name: Lindenman Well No. B-1

Location: CN/2-N/2-NE Sec. 6 Twp. 7 Rge. (E)(W) 25

County: Graham Total Depth 3850' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

287'--8 5/8" Surface casing, cement circulated.

3846'--5 1/2" Production casing, cemented on bottom with 125 Sx. Well plugged back to 3710'. Top perforations from 3704' to 3707'.

Sand well back to 3675' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent