

State of Kansas



15-065-30133-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

123  
OCT 23 1967  
10-23-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Duane Born of Paine Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Paine Drilling Company, Incorporated,

Complete Address: Box "D", Hill City, Kansas.

Lease Name: Wilcox Well No. 1

Location: NE-SE-NW Sec. 7 Twp. 7 Rge. (E)(W) 25

County Graham Total Depth 3860' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

256'--7" OD Casing, cement circulated with 125 Sx.  
Dakota section from 970' to 800'. (Well has been temporarily abandoned).

Squeeze well staging first, 55 Sx cement plus 6% gel, follow with 17 Bbls.  
rotary mud then 15 Sx. cement and follow with 7 Bbls. mud then 10 Sx.  
cement to bottom of cellar.

Very truly yours,

Conservation Division Agent