



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 20 1963  
 2-20-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers Inc., has this

date requested permission to plug the following described well:  
C & G Drilling Co.,

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Co.,

Complete Address: 107 Rule Bldg., Wichita, Kansas.

Lease Name: Goodrow Well No. 1

Location: SW-SW-SW Sec. 17 Twp. 7 Rge. (E) (W)

County Graham Total Depth 3920' Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Finch was instructed to plug the well as follows:

Sand well back to 3900', set 4 Sx cement w/dump bailer. Pull  
5 1/2" to 550', circulate heavy gel mud and displace 20 Sx cement  
thru 5 1/2". Pull 5 1/2" to 270', displace 20 Sx cement thru 5 1/2".  
Pull 5 1/2" set bridge and 10 Sx cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
 Conservation Division Agent