



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 7-1-63 1963

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling has this

date requested permission to plug the following described well:

C & G Drilling Company

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Company,

Complete Address: 107 Rule Building, Wichita, Kansas.

Lease Name: Kendall Well No. 1

Location: NE-NE-NW Sec. 20 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3944 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

290'--8 5/8" Surface pipe, cement circulated.

3944'--5 1/2" cemented with 175 Sx. Top plug @ 3723'. Top per-
forations @ 3713.

Sand well back to 3705' and set 5 Sx cement with dump bailer.
Pull 5 1/2" to 540', circulate heavy gel mud and displace 20 Sx
ement thru casing. Pull 5 1/2" to 280' and displace 20 Sx cement
thru casing. Pull 5 1/2", set bridge and 10 Sx cement to bottom
of cellar.

Very truly yours,
W. L. Nichols
Conservation Division Agent