

State of Kansas



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
7-15-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Kendall Well No. 1

Location: N/2-N/2-NW/4 Sec. 20 Twp. 7 Rge. (E)(W) 25

County: Graham Total Depth 3900 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

310'---8 5/8" Surface pipe, cement circulated with 200 Sx.  
Top of Dakota section @ 1070'.

Circulate hole with heavy mud. Pull DP to 1295' and displace 100 Sx.  
cement thru DP. Pull DP to 330' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent