

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: (Oil) Gas, (Dry) SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

15-163 21415-00-00

OPERATOR Ron's Oil Operations Lic # 6861

API NO. 15-195-20,884

ADDRESS Rt 1 Box 76

COUNTY Rooks

Hill City, Ks 67642

FIELD Hrabe

\*\*CONTACT PERSON Ronald Nickelson

PROD. FORMATION Kansas City

PHONE 913-674-2409

LEASE Hrabe

PURCHASER

WELL NO. 1

ADDRESS

WELL LOCATION SE NW NW

DRILLING Lawbanco Drilling

1250' Ft. from North Line and

CONTRACTOR

710' Ft. from W Line of

ADDRESS Natoma, Kansas


the SEC 25 TWP. 8 RGE. 17

PLUGGING Allied Cementing

CONTRACTOR

ADDRESS Russell, Ks. RW-KCC

WELL PLAT



KCC [checked] KGS [checked] (Office Use)

TOTAL DEPTH 3439 PBTD

SPUD DATE 9-1-81 DATE COMPLETED 9-7-81

ELEV: GR 1978 DE 1981 KB 1983

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 268 DV Tool Used? no

AFFIDAVIT

STATE OF Kansas, COUNTY OF Graham SS, I,

Ronald Nickelson OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS (FOR)(OF)

OPERATOR OF THE Hrabe LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON


SAID LEASE HAS BEEN COMPLETED AS OF THE 1st DAY OF Dec, 1981, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) Ronald Nickelson

SUBSCRIBED AND SWORN BEFORE ME THIS 14th DAY OF May, 1983.



Jean L. Wasinger NOTARY PUBLIC

MY COMMISSION EXPIRES: 11-9-85

\*\*The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by State Corporation Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

MAY 17 1983 5-17-1983 CONSERVATION DIVISION Wichita Kansas

**SIDE TWO**

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
	Elec Log			
	Depth	Datum		
Anhydrite	1286	+ 697		
B. Anhydrite	1320	+ 663		
Topeka LS	2872	-889		
Heebner Sh	3090	-1107		
Toronto <del>Sh</del> Ls	3112	-1129		
Lansing Fm	3133	-1150		
B. Kansas City	3376	-1393		

**Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Production	7 7/8	4 1/2	10 1/2	3437	60/40pos	150	2% salt

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		3340
			4		3364, 3310-13
					3297-3301
					3234-36
					3058-61

**TUBING RECORD**

Size	Setting depth	Packer set at
2"	3435	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
1500 gal 15% acid, retreated 3000 gal 28%	3364, 3340
1500 gal 15% acid, retreated 3000 gal 28%	3310-13, 3298-3301
3000 gal 28 % acid	3217, 3234
500 gal	3058-61

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
10-1-81	Pumping	
<b>RATE OF PRODUCTION PER 24 HOURS</b>	Oil	Gas
	1 bbls.	MCF
	Water	Gas-oil ratio
	% 20	bbls. CFPB
Disposition of gas (vented, used on lease or sold)		Perforations
Vented		