

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-20,482-50-50 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Martin Oil Producers, Inc. OPERATOR'S LICENSE NO. 5097

ADDRESS 150 N. Main, #1010, Wichita, KS 67202 PHONE # (316) 264-0352

LEASE (FARM) McMullen "A" WELL NO. 1 WELL LOCATION NW SW NW COUNTY Rooks

SEC. 34 TWP. 8S RGE. 17 ~~(E)~~(W) TOTAL DEPTH 3458 PLUG BACK TD 3451

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 207' CEMENTED WITH 200 SACKS

CASING SIZE 5 1/2" SET AT 3451' CEMENTED WITH DV shoe 1341 -300 3431 -200 SACKS

PERFORATED AT 3236-3238' 4 holes per foot

CONDITION OF WELL: GOOD POOR CASING LEAK 2601' JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING pump 50 sacks cement down casing, follow 500# cotton

seed hulls, then 200 sacks cement to top. Pump surface if possible, use

60-40 pozmix cement 6% gel

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN _____ as soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

William S. Stockstill PHONE # (316) 257-2227

ADDRESS Box 127, Lyons, KS 67554

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287

ADDRESS Box 428, Hays, KS 67601 PHONE # (913) 625-3431

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]
(Operator or Agent)

DATE: November 16, 1989

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1989

CONSERVATION DIVISION
Wichita

4



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
 KEITH R. HENLEY CHAIRMAN
 RICH KOWALEWSKI COMMISSIONER
 MARGALEE WRIGHT COMMISSIONER
 JUDITH MCCONNELL EXECUTIVE DIRECTOR
 FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
 FEB 20 1990
 EXPIRES

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

November 20, 1989

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

Martin Oil Producers, Inc.
 150 N. Main, #1010
 Wichita, KS 67202

McMullen "A" 1
 NW SW NW
 Sec. 34-08-17W
 Rooks County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
 Shari Feist Albrecht
 Director

District: #4 2301 E. 13th

 Hays, KS 67601

 (913) 628-1200
