

15-163-19126-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER comp1 5/64
LEASE NAME Doane
WELL NUMBER 10
SPOT LOCATION W/2 NE SE
SEC. 34 TWP. 8S RGE. 16W (E) or (W)
COUNTY Rooks
Date Well Completed 5/64
Plugging Commenced 7/8/88
Plugging Completed 7/8/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company/Co-Co, Inc.
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202
PHONE # () 267-3241 OPERATORS LICENSE NO. 6033

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 - Hays

Is ACO-1 filled? no If not, is well log attached? yes

Producing formation LKC Depth to top 3054' bottom 3294' T.D. 3355'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	218'	-
				5 1/2"	3354'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran wireline to 1555'. Perf Anhydrite @ 1350'. Pumped down 5 1/2" csg. w/50 sx. 60-40 Pozmix w/4% gel, 1/4#/sx. Flocele & 100 sx. Lite w/2 sx hulls w/1/4#/sx. Flocele. Max 300 psig, ISIP 100 psig. Pumped down 8 5/8" csg. w/50 sx. Lite w/1/4#/sx. Flocele & 1 sx hulls. Max 500 psig, ISIP 300 psig. JC 12:05 p.m. 7/8/88. Witnessed & approved by Dennis Hamel w/KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address 250 N. Water, Suite 300; Wichita, KS 67202


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Larry M. Jack, Production Manager (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: Larry M. Jack STATE CORPORATION COMMISSION
Wichita, Kansas

(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 1 day of August, 1988



Kerran Redington
Kerran Redington, Notary Public

My Commission expires 2/6/90

RECEIVED
STATE CORPORATION COMMISSION
8/2/88
AUG 2 1988

CONSERVATION DIVISION
Wichita, Kansas

15-163-19126-00-00

ROTARY DRILLING LOG

WELL FILE

OPERATOR:	Max Cohen	COM:	4-30-64
CONTRACTOR:	D & D Drilling Company, Inc.	COMP:	5-6-64
WELL:	Doane No. 10	ELEV:	1958 R.B.
LOCATION:	Approx. W/2 NE SE		1955 D.F.
COUNTY:	Rooks, Kansas		1953 G.L.

Formations	Depth	Remarks
Sand & Shale	1206'	Set 8 joints of 8 5/8" surface casing at 218', cemented with 190 sacks HA-5.
Anhy.	1242'	
Shale	1750'	
Shale & Lime	2965'	
Lime	3043'	
Lime & Shale	3148'	Set 119 joints of 5 1/2" casing at 3354', cemented with 125 sacks Salt Sat. Cement.
Lime	3355'	
Rotary Total Depth	3355'	

A F F I D A V I T

State of Kansas)
) SS
 County of Sedgwick)

James R. Daniels, of lawful age, being duly and solemnly sworn on oath says: I am a resident of Wichita, Sedgwick County, Kansas, and I hereby know and on oath state, the above drilling log covering the Doane No. 10 located in the approximate W/2 NE SE of Section 34-T8S-R16W, Rooks County, Kansas, is true and correct to the best of my knowledge and belief. Further affiant saith not.

James R. Daniels

 James R. Daniels

Subscribed and sworn to before me this 13th day of May, 1964.

My Commission Expires:
11-18-66

RECEIVED
 CONSERVATION COMMISSION
 Colleen Chapple - Notary Public

AUG 2 1988
 CONSERVATION DIVISION
 Wichita, Kansas
 8/2/88