

15-163-19125-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL FILE

API NUMBER n/a
LEASE NAME Doane
WELL NUMBER 9
SPOT LOCATION S/2 SW SE
SEC. 34 TWP. 8 RGE. 16 (X) or (W)
COUNTY Rooks
Date Well Completed 6/4/64
Plugging Commenced 4/8/85
Plugging Completed 4/8/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company
ADDRESS 250 North Water, Suite 300, Wichita, Kansas 67202
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Input
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays; District #6

Is ACO-1 filed? No If not, is well log attached? No

Producing formation LKC Depth to top 3031 bottom 3272 T.D. 3330

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	222'	---
				5 1/2"	3329'	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Spotted 150 sacks 50/50 Pozmix w/4% gel and 3 sacks hulls @ 1133'. Spotted 50 sacks cement (same mix) w/1 sack hulls. Pulled tubing to 384'. Pumped 110 sacks cement (same mix) w/2 sacks hulls; circ. 10 sacks. Pulled tubing out hole. Hooked up to 5 1/2" & 8 5/8" annulus and instantly pressured to 1200# and held. Hooked back to 5 1/2" casing and pumped 140 sacks cement (same mix) w/1 sack hulls. SIP - 900#. Cement pumped = 4849' of 5 1/2" casing capacity. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address 250 North Water, Suite 300; Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Pat Canaday, Hill City District, Jr. Engineer (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as **RECEIVED** that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) [Signature]
(Address) P.O. Box 130, Hill City, KS. 67642

SEP 13 1985
9/13/85
SUBSCRIBED Pat Canaday before me this 18 day of July, 1985
Wichita, Kansas



My Commission expires: 6/30/87

Donna Gerstner
Notary Public