

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-20,482-65-0

LEASE NAME McMullen "A"

WELL NUMBER 1

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 34 TWP. 8S RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 2/14/73

Plugging Commenced 11/28/89

Plugging Completed 11/30/89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Martin Oil Producers, Inc.

ADDRESS 150 N. Main, #1010, Wichita, KS 67202

PHONE# (316) 264-0352 OPERATORS LICENSE NO. 5097

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Shari Feist

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation Kansas City Depth to Top 3158' Bottom 3394' T.D. 3458'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	207	0
				5 1/2"	3451	0

STATE CORPORATION COMMISSION  
 RECEIVED  
 DEC 26 1989  
 CONSERVATION DIVISION  
 WICHITA, KANSAS  
 2/26/89

Describe in detail the manner in which the well was plugged, indicating where and how it was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each.

See Attached Sheet

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Box 428, Hays, KS 67601

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. S. Martin, President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 150 N. Main, #1010  
 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of Dec., 19 89

[Signature]  
 Notary Public

My Commission Expires: \_\_\_\_\_



15-163-20482-00-00



MARTIN OIL PRODUCERS, INC.

1010 UNION CENTER • WICHITA, KANSAS 67202

(316) 264-0352

#1 McMullen "A"  
Sec. 34-8S-17W  
Rooks County, Kansas

WELL PLUGGING RECORD PAGE 2

- 11/28/89 Halliburton tied on to back side, pumped 12 sacks 60-40 pozmix cement in. Shut in at 400# pressure. Tied on to 5 1/2" casing, pumped 50 sacks 60-40 pozmix cement, then started 500# of cotton seed hulls and 213 sacks of 60-40 pozmix at 350# max pressure. Shut in at 100#.
- 11/30/89 Halliburton ran wire line to top of cement in casing. Found cement at 722'. Dumped 4 yards ready mix cement in casing & filled to surface. Cut surface pipe off 5' below ground level.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1989

CONSERVATION DIVISION  
Wichita, Kansas

12/20/89