


15-163-01340-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rocks _____ County. Sec. 34 Twp. 8 Rge. 16 (E) WestW
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. S. SE SE
 Lease Owner Max Cohen
 Lease Name Doane Well No. 1
 Office Address Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed 7-25-42
 Application for plugging filed 11-7, 1951
 Application for plugging approved Oct. 27, 1951
 Plugging commenced 10-16-51
 Plugging completed 10-20-51
 Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August, 1951
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty
 Producing formation K C Depth to top 3104 Bottom 3140 Total Depth of Well 3140 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"		2156'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from 3140' to 3090' and ran 4 sacks of cement. Checked hole and found mud had fallen in behind pipe. Pumped in 160' of mud and pumped in 20 sacks of cement at 210'. Mudded hole to 20' and set 5' rock bridge. Pumped in 10 sacks of cement. Plugging completed.

11/13/51

RECEIVED
 NOV 15 1951
 CONSERVATION DIVISION
 STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
 Correspondence regarding this well should be addressed to Percy Parsons
 Address Halstead, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Max Cohen (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Max Cohen

203 Brown Bldg. Wichita, Kans
 (Address)

SUBSCRIBED AND SWORN to before me this 7 day of Nov. 1951

Jack A. Paulsen
 Notary Public.

My commission expires Jan. 31, 1955

PLUGGING
 FILE SEC 34 T 8 R 16
 BOOK PAGE 120 LINE 6

15-163-01340-00-00

Walter Groneman
Doane No. 1

c 5/2 SEC. 34-8-16
SE SE
Rooks County, Kansas

Total Depth (top K. C.) 3140'
Comm. 7-10-42 Comp. 7-25-42
Contractor, Three Way Drilling Company
Issued July 27, 1942

Elevation 1903

Production

Casing: Surface
Oil String, 3140' 5-3/16"

Figures indicate bottom of Formations:

Shale and shells	250
shale & sand	590
shale & shells	625
red bed	705
shale & shells	816
red bed & iron	960
red shale	1199
shale	1225
anhydrite	1276
shale	1749
lime	1786
shale	1833
shale & lime	1938
shale & shells	2005
shale & lime	2050
lime	2065
shale & redrock	2090
lime & iron	2110
lime	2215
lime & redrock	2300
lime	2440
lime & shale breaks	2555
lime	2595
lime & redrock	2635
shale & shells	2693
shale & lime	2755
lime	2783
shale & shells	2840
lime	2870
breaks lime shells	2932
lime	2998
lime & shale	3071
lime	3087
lime & shale	3113
K. C. Lime	3120
lime	3140

Tops by Gulf Oil

Topeka 2847
Oread 3099 base
Lansing 3104

PLUGGING
FILE SEC 34-8-16 R 16
BOOK PAGE 170 6

RECEIVED
NOV 13 1951
DIVISION
11/13/51