

15-163-22109-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 35 TWP. 8S RGE. 16 E/W
Location as in quarters or footage from lines:)
NE NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Thornton E. Anderson
Lease Name McFadden Well No. 2
Office Address 840 First National Bank Bldg., Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed September 11, 1983
Application for plugging filed yes
Plugging commenced September 11, 1983
Plugging completed September 11, 1983
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel
Producing formation _____ Depth to top _____ bottom _____ T.D. 3578
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	1312	8 5/8	1304'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Hole was plugged with 50/50 pozmix, 6% gel,
3% CaCl as follows:
1st plug @ 1320' with 20 sacks
2nd plug @ 750' with 100 sacks
3rd plug @ 250' with 40 sacks
4th plug & solid bridge @ 40' with 10 sacks
10 sacks in mousehole, 10 sacks in rathole

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1983
A/15/83
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cement, Russell, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss. Contractor for
John Jay Darrah, Jr., President (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

By John Jay Darrah, Jr.
Mallard Drilling Co., Inc.
(Signature) 405 Century Plaza
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 83

Dianne R. Fowler
Dianne R. Fowler, Notary Public.

My Commission expires: 8/25/84

15-163-22109-00-00

D R I L L E R S L O G

COMPANY: THORNTON E. ANDERSON
 CONTRACTOR: MALLARD DRILLING CO., INC.
 405 Century Plaza
 Wichita, Kansas 67202

WELL NAME: McFADDEN #2
 DESCRIPTION: NE NW SE
 Sec. 35-8S-16W
 COUNTY: Rooks
 ELEVATION: 2040 KB
 COMPLETED: September 11, 1982

RIG NO.: 1
 TOTAL DEPTH: 3578
 COMMENCED: September 3, 1983


CASING RECORD:
 23 joints new 8 5/8" 23# surface

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, Sand	0	1303	Ran 1304' new 23# 8 5/8" surface casing; set and cemented with 425 sacks 60/40 pozmix, 3% CaCl, 2% gel at 1312'. Cement circulated. Plug down at 5:15 p.m., September 4, 1983. Ran 1 electric log Ran 4 drill stem tests Hole plugged with 50/50 pozmix, 6% gel, 3% CaCl as follows: 20 sacks @ 1320'; 100 sacks @ 750'; 40 sacks @ 250'; 10 sacks and solid bridge @ 40'; 10 sacks in rathole; 10 sacks in mousehole. Plugging completed at 10:30 p.m., September 11, 1983.
Anhydrite	1303	1345	
Shale & lime	1345	2972	
Lime	2972	3578	

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the McFadden #2 well, to the best of my knowledge.


 John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 14 day of September, 1983.


 Dianne R. Fowler, Notary Public

My Commission Expires:
 August 25, 1984

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 15 1983
 9/15/83
 CONSERVATION DIVISION
 Wichita, Kansas