


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-163-00309-0000  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County. Sec. 34 Twp. 8S Rge. (E) 17 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE, NE, SW  
Lease Owner Jones, Shelburne & Farmer, Inc.  
Lease Name Diehl Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed November 25 1950  
Application for plugging filed November 25 1950  
Application for plugging approved November 25 1950  
Plugging commenced November 25 1950  
Plugging completed November 25 1950  
Reason for abandonment of well or producing formation Dry  
If a producing well is abandoned, date of last production Never Produced 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty  
Producing formation Depth to top Bottom Total Depth of Well 3,551 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	167'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Hole filled with heavy mud.
- Halliburton plug pushed to 160 feet.
- One sack hulls dumped in and washed to top of plug with water.
- Fifteen sacks cement mixed and spotted on top of hulls.
- Second Halliburton plug shoved to 40 feet.
- One-half sack Hulls dumped on top of hulls.
- Ten sacks cement mixed and hole filled to top with same.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1950 11-30-1950  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Jones, Shelburne & Farmer, Inc.  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
John O. Farmer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) John O. Farmer  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of November, 1950.  
Phyllis Bethany Notary Public.

My commission expires June 3, 1953  
23-5091-s 8-50-10M

PLUGGING  
FILE SEC 34 T 8 R 17a  
BOOK PAGE 46 LINE 1

# Jones, Shelburne & Farmer, Inc.

Russell, Kansas

15-163-00309-00-00

## CONTRACTOR'S VERIFIED LOG

Operator JONES, SHELBURNE & FARMER, INC Farm Name DIEHL Well No 1  
 Location NE, NE, SW SECTION 34-8S-17W  
 Pool Name \_\_\_\_\_ County ROOKS State COUNTY  
 Commencement Date 11/14/50 Completion Date 11/25/50

### Log of Well

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
0	650	Shale and Shells		
650	1030	Shale and Sand		
1030	1320	Shale and Shells		
1320	1365	Anhydrite		
1365	1725	Shale and Shells		
1725	3150	Shale and Lime		
3150	3417	Lime		
3417	3520	Lime and Shale		
3520	3551	Lime		
	3551	Total Depth		
TOPS:				
	1320	Anhydrite		
	3125	Heebner		
	3141	Toronto		
	3165	Kansas City		
	3472	Conglomerate		
	3514	Arbuckle		
<p>3410-17 Drill Stem Test                      Open 20 minutes.                      Blew for 10 min. weak.                      Rec. 10' mud with pin-                      points of oil. BHP                      780# in 10 minutes.</p>				

STATE CORPORATION COMMISSION  
 NOV 30 1950  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 11/30/50

**PLUGGING**  
 FILE SEC 34-8-17W  
 BOOK PAGE 40

(Log Well Continued)

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
3230	3230			
3230	3230			
3230	3230			
3230	3230			
3230	3230			
3230	3230			
3230	3230			
3230	3230			
3230	3230			
3230	3230			Total Depth

Was Well to be deepened by another Contractor? \_\_\_\_\_

**CASING LEFT IN HOLE AFTER COMPLETION OR ABANDONMENT**

Size	Wt.	Grade	Range	Thread	FOOTAGE					
					Delivered	Run	Set At	Unused	Pulled	Left in Hole
8 5/8"						160'			None	160'

Deviation From Vertical Data Is Correct as Shown  
 Company Superintendent  
 (This space for Company use)

The foregoing Well Log and other data are correct.

**JONES, SHELburnE & FARMER, Inc.**  
 Contractor

By *John Farmer*

JONES, SHELburnE & FARMER, Inc.  
 12-103-0030