

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
211 NORTH BROADWAY  
WICHITA, KANSAS

15-163-00421-00-00

WELL PLUGGING APPLICATION FORM

File One Copy

Lease Owner (Applicant) Murfin Drilling Co. Address 507 Union Nat. Bank Bldg - Wichita, Ks.

Lease (Farm Name) Dancer Well No. 1

Well Location NE NE NW Sec. 4 Twp. 8 Rge. 17W(E) - (W)

County Rooks Field Name (if any)

Total Depth 3392 Oil xx Gas  Dry Hole

Was well log filed with application? yes If not, explain:

Date and hour plugging is desired to begin March 25, 1956

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner L. M. McCord

234 Fossil Address Russell, Ks.

Plugging Contractor Earl Miller

Plugging Contractor's License No.

Address Great Bend, Ks.

Invoice covering assessment for plugging this well should be sent to

Murfin Drilling Co. Address same as above

and payment will be guaranteed by applicant.

Fred Murfin  
Applicant or Acting Agent

Date March 20, 1956

**PLUGGING**  
FILE SEC 4 T 8 R 17W  
BOOK PAGE 47 LINE 14

321-56



STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 211 NORTH BROADWAY  
 WICHITA, KANSAS

15-163-00421-00-00

March 21, 1956

Well No. 1  
 Lease Dancer  
 Description NE 1/4 NW 1-8-17W  
 County Hooker  
 File No. 17-14

Murfin Drilling Company  
 507 Union National Bank Bldg.  
 Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION

By S. S. Greider  
 S. S. Greider  
 WELL PLUGGING SUPERVISOR

cc:  
 District Plugging Supervisor

State of Kansas }  
 County of Sedgwick } ss:

3-21-56

**PLUGGING**  
 FILE SEC 4 Y 8 R 17W  
 BOOK PAGE 47 LINE 14

I, W. R. Murfin of the Murfin Drilling Company  
 upon oath-state that the above and foregoing is a true and correct copy of the log of the Dancer #1 well.

Subscribed and sworn to before me this 12th day of March 19 52

My Commission Expires: 6-4-55

W. R. Murfin  
Abby Heimerman  
 NOTARY PUBLIC

WELL LOG

15-163-00421-00-00

COMPANY Murfin Drilling Co.

SEC. 4 T. 8 R. 17W

FARM Dancer NO. 1

LOC. NE NE NW

TOTAL DEPTH 3355

COMM. 2-9-52


COMP. 2-19-52

COUNTY Rooks

KANSAS

SHOT OR TREATED 1000 gal. acid  
CONTRACTOR Murfin Drilling Co.

ISSUED



CASING

20	10	
15	8	128
12	6	
13	5	3353

ELEVATION 1881 DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 128 shale-shells
- 550 shale
- 580 sand
- 735 shale
- 1000 sand
- 1050 sand-shale
- 1273 red bed
- 1304 Anhydrite
- 1550 shale
- 1675 shale-lime
- 1570 lime
- 1900 brkn. lime
- 2065 shale-lime
- 2155 lime
- 2630 shale-lime
- 2764 shale
- 3270 lime
- 3355 lime-shale


DST #1 3057-3108 1 hr. 8' mud, 300# BHP

DST #2 3143-58 30 min. 60' slightly oil cut mud, 270' heavily oil cut mud, 30' water, 1150# BHP

Cable Tool Information - Drilled to 3387'. Slight trace oil and 10 bbls. water per day. Plugged back to 3180'. Perforated 3148-51. No fluid. Perforated 3148-52 and shut down 14 hrs. Had 300' water and 1/2 bailer oil. Acidized 1000 gal. Hole filled 2300' oil in 14 hrs. No water. Test - Swabbed 26 1/2 bbls. per hr. No water.

State of Kansas }  
County of Sedgwick } ss:

3-21-56



I, W. R. Murfin of the Murfin Drilling Company

upon oath-state that the above and foregoing is a true and correct copy of the log of the Dancer #1 well.

*W.R. Murfin*

Subscribed and sworn to before me this 12th day of March 19 52

My Commission Expires: 6-4-55

*Abby Heimerman*  
NOTARY PUBLIC