

LEASE NAME HATTRUP

WELL NUMBER 1-30

2490' FSL Ft. from S Section Line

2490' FEL Ft. from E Section Line

SEC. 30 TWP. 26S RGE. 39W (E) or (W)

COUNTY HAMILTON

Date Well Completed 09/08/51

Plugging Commenced 02/06/06

Plugging Completed 02/07/06

RECEIVED

FEB 17 2006

KCC WICHITA

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (727) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/28/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3325' Bottom 2466' T.D. 2595'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2408'	2466'	10" 7.5	540'	0'
				7"	2499'	652'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

2/6-7/06 Witnessed by K Jehlik, KCC. Set CIBP @2350' KB, spot 20' cmt. Revise PBTD @2330'.NU, load hole w/6 bbl mud & 20 sx cmt plug 1900'-1650' & 25 bbl mud 1650'-0, calc free pt on 4 1/2" csg, cut at 1414'.Load hole w/30 bbl mud. Cut 7" csg@ 652'. Circ w/mud &75 sx cmt plug 650'-500' & displ w/10 bbl mud. Fill hole w/5 bbl mud to 40', pmp 15 sz cmt plug 40' to 0', cut 10 3/4" csg 3' bgl, weld on trash cover ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



AND SWORN TO before me this 13th day of February, 20 06
My Commission Expires: 4/2/09 Notary Public Deborah Pollock

[Handwritten mark]