

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

MAR 09 2006

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

\*\* Approx. 160S & 110E of

Lease Operator: Lario Oil & Gas Company
Address: 301 S. Market St.; Wichita, KS 67202
Phone: (316) 265-5611 Operator License #: 5214
Type of Well: D&A Docket #: (If SWD or ENHR)
The plugging proposal was approved on: 01/10/2006 (Date)
by: Herb Deines - Hays (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-065-23123-00-00
Lease Name: Anderson-Murphy
Well Number: 1-36
Spot Location (QQQQ): \*\* - W2 - W2 - NW
1480 Feet from North / South Section Line
440 Feet from East / West Section Line
Sec. 36 Twp. 07 S. R. 25 East West
County: Graham
Date Well Completed: 01/10/2006
Plugging Commenced: 01/10/2006
Plugging Completed: 01/10/2006

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 8-5/8", 288', none.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged with 200 sks 60/40 (Poz)+6% Gel + 1/4# flocele as follows:

1st plug - 25 sks @ 2200'; 2nd plug - 100 sks @ 1425'; 3rd plug - 40 sks @ 350'

Top plug - 10 sks @ 40' to surface; Mouse hole - 10 sks & Rat hole - 15 sks

Name of Plugging Contractor: Allied Cementing Co. Murfin Drilling Co. License #: 30606
Address: P.O. Box 31; Russell, KS 67665

KCC Blm 3-10-06 Per CP 2/3

Name of Party Responsible for Plugging Fees: Lario Oil & Gas Co.

State of Kansas County, Sedgwick, ss.

Jay G. Schweikert, Operations Engineer

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

Jay G. Schweikert

(Address)

301 S. Market St.; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 8th day of March, 2006

KATHY L. FORD Notary Public - State of Kansas My Appt. Expires 10-22-06

Kathy L. Ford Notary Public

My Commission Expires: 10-22-06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm