

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

MAR 09 2006

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Glacier Petroleum, Inc. Address: P.O. Box 577 Emporia, KS 66801-0577 Phone: (620) 342-1148 Operator License #: 05721 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 02/26/2006 by: Mike Wilson (KCC District Agent's Name) Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): Cher (Catt SD) Depth to Top: 2362 Bottom: 2379 T.D. 2562

API Number: 15-017-20014-00-00 Lease Name: Browning Well Number: #1 Spot Location (QQQQ): NW - NE - NE - 4950 Feet from North / South Section Line 990 Feet from East / West Section Line Sec. 24 Twp. 22 S. R. 9 East West County: Chase Date Well Completed: 11/04/1971 Plugging Commenced: 02/26/06 Plugging Completed: 03/02/2006

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Cher (Catt SD), Oil, 2362, 2372, 5 1/2", 2437, 0.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

02/26/2006, Set bottom plug of sand and cement (3 sx) from 2430 ft to 2310 ft /w dump bailer, filled casing /w gel, 03/02/2006, RIH /w 2 3/8 tubing to 250 ft., circ cement inside casing to surface, TOOH /w tubing, RI Anuulas /w 3/4, cement surface to casing, Topped off, (Consolidated Tk # 08369, 60 sx total), started plugging surface plug at 10:00 am on 03/02/2006 and finished at 11:00 am on 03/02/2006.

Name of Plugging Contractor: Glacier Well Service License #: 05721 Address: P.O. Box 577, Emporia, KS 66801-0577 Name of Party Responsible for Plugging Fees: Glacier Petroleum, Inc. State of Kansas County, Lyon, ss. J.C. Hawes

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) P.O. Box 577 Emporia, KS 66801-0577



SUBSCRIBED and SWORN TO before me this 8th day of March, 2006. Sally L. Linhart Notary Public My Commission Expires: 6/11/2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]