

RECEIVED

MAR 09 2006

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

Lease Operator: Glacier Petroleum, Inc.
Address: P.O. Box 577 Emporia, KS 66801-0577
Phone: (620) 342-1148 Operator License #: 05721
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 02/26/2006 (Date)
by: Mike Wilson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Cher (Catt SD) Depth to Top: 2435 Bottom: 2450 T.D. 2500

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-017-20019-00-01
Lease Name: Browning
Well Number: # 2 OWWO
Spot Location (QQQQ): NW - SE - NE -
3630 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 24 Twp. 22 S. R. 9 East West
County: Chase
Date Well Completed: 12/18/2006 *1984 Per Scout Card*
Plugging Commenced: 02/26/06
Plugging Completed: 03/02/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cher (Catt SD)	Gas	2442	2448	5 1/2"	2500	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

02/26/2006, Set bottom plug of sand and cement (3 sx) from 2482 ft to 2390 ft /w dump bailer, filled casing /w gel, 02/28/2006,
set 50 ft sand and cement plug from 650 ft to 600 ft. /w dump bailer, perf casing at 250 ft., 03/02/2006, circ cement from 250 ft to
surface (Consolidated Tk # 08368, 60 sx total), started plugging surface at 12:30 pm on 03/02/2006 and finished at 2:00 pm
on 03/02/2006.


Name of Plugging Contractor: Glacier Well Service License #: 05721
Address: P.O. Box 577, Emporia, KS 66801-0577
Name of Party Responsible for Plugging Fees: Glacier Petroleum, Inc.
State of Kansas County, Lyon, ss.
J.C. Hawes

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) J.C. Hawes
(Address) P.O. Box 577 Emporia, KS 66801-0577

SUBSCRIBED and SWORN TO before me this 8th day of March, 2006
Sally L. Linhart My Commission Expires: 6/11/2007
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas



Ben