

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-27595-00-00

Spot: S2SWNW

Sec/Twnshp/Rge: 27-33S-14E

2860 feet from S Section Line, 4620 feet from E Section Line

Lease Name: EDDS

Well #: 20

County: MONTGOMERY

Total Vertical Depth: 750 feet

Operator License No.: 33074

Op Name: DART CHEROKEE BASIN OPERATING

Address: 600 DART RD PO BOX 177

MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	750	0	
SURF	7	20	0	

35⁰⁰

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/20/2005 8:00 AM

Plug Co. License No.: 30670

Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP

Proposal Rcvd. from: TONY WILLIAMS

Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed
Plugging
Method:

Run 1 inch cement string to TD and cement from bottom to top.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 12/20/2005 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The plugging contractor attempted to remove the 1 inch tubing. The tubing pulled apart at 310 ft. Therefore, a 1 inch cement string was run inside the 2.875 inch casing to 310 ft. A second cement string was lowered down the annular space between the 2.875 inch casing and the surface pipe to 425 feet. The well was filled from bottom to top thru these 1 inch strings of pipe. The 1 inch pipe was removed and then additional cement added to bring cement to top of well. 154 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DISTRICT #3

JAN 31 2006

AMD

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

RECEIVED
MAR 10 2006
KCC WICHITA

INVOICED
DATE 3-13-06
INV. NO 2006061261

Form CP-2/3