

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-22691-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 27-33S-14E  
3770 feet from S Section Line, 3310 feet from E Section Line  
Lease Name: EDDS Well #: 7  
County: MONTGOMERY Total Vertical Depth: 750 feet

Operator License No.: 33074  
Op Name: DART CHEROKEE BASIN OPERATING  
Address: 600 DART RD PO BOX 177  
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	750	0	
SURF	7	20	0	

#35<sup>00</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2005 8:00 AM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed Plugging Method: Plug well by connecting to wellhead and squeezing cement into well. When full of cement, shut the well in with pressure.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/22/2005 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1 inch string of pipe was run inside the 2.875 inch casing to 725 ft. The well was filled from bottom to top thru this 1 inch string of pipe. The 1 inch pipe was removed and then additional cement added to bring cement to the top of well. The well was cut off below plow depth and the location restored. Altogether, 77 sacks of portland cement were used to plug well.

RECEIVED  
KCC DISTRICT #3  
JAN 25 2006 *AMB*  
CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning  
(TECHNICIAN)

RECEIVED  
MAR 10 2006  
KCC WICHITA

INVOICED  
DATE 3-13-06  
# 2006061261