

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-22693-00-00
Spot: NENWNW Sec/Twnshp/Rge: 27-33S-14E
4760 feet from S Section Line, 4230 feet from E Section Line
Lease Name: EDDS Well #: 9
County: MONTGOMERY Total Vertical Depth: 750 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	750	0	
SURF	7	20	0	

\$35⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2005 8:00 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed Plugging Method: Plug well by connecting to wellhead and squeezing cement into well. When full of cement, shut the well in with pressure.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 12/20/2005 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1 inch string of pipe was run inside the 2.875 inch casing to 725 ft. The well was filled from bottom to top thru this 1 inch string of pipe. The 1 inch pipe was removed and then additional cement added to bring cement to the top of well. The well was cut off below plow depth and the location restored. Altogether, 28 sacks of portland cement were used to plug well.

RECEIVED
KCC DISTRICT #3
JAN 25 2006 AMD
CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

RECEIVED
MAR 10 2006
KCC WICHITA

INVOICED
DATE 3-13-06
2006061261