

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-24146-00-00
Spot: N2NW Sec/Twnshp/Rge: 27-33S-14E
4510 feet from S Section Line, 3960 feet from E Section Line
Lease Name: EDDS Well #: 10
County: MONTGOMERY Total Vertical Depth: 750 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	750	0	
SURF	7	20	0	

\$35⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2005 8:00 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed Plugging Method: Run 1 inch cement string to TD and cement from bottom to top.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 12/16/2005 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

310 ft of 1 inch pipe was lowered down the inside of the 2.875 inch casing. 425 ft of 1 inch pipe was lowered down the annular space between the 2.875 inch casing and the surface pipe. The well was filled from bottom to top thru these 1 inch strings of pipe. The 1 inch pipe was removed and then additional cement added to bring cement to the top of well. The well was cut off below plow depth and the location restored. Altogether, 154 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DISTRICT #3

JAN 25 2006 *AMB*

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)

RECEIVED
MAR 10 2006
KCC WICHITA

INVOICED
DATE 3-13-06
INV. NO. 2006061261