

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21366-00-00

Spot: NWNENE

Sec/Twnshp/Rge: 25-33S-16W

380 feet from N Section Line,

975 feet from E Section Line

Lease Name: MERRILL TRUST

Well #: 1-25

County: COMANCHE

Total Vertical Depth: 5350 feet

Operator License No.: 5050

Op Name: HUMMON CORPORATION

Address: 950 N. TYLER
WICHITA, KS 67212

String Size Depth (ft) Pulled (ft) Comment

CIBP 4700 WITH 2 SX CMT

PROD 5.5 5340 720 WITH 200 SX CMT

SURF 13.38 318 300 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/06/2006 10:00 AM

Plug Co. License No.: 5105

Plug Co. Name: CLARKE CORPORATION

Proposal Revd. from: JOHN SWINFORD

Company: CLARKE CORPORATION

Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4700' & 2 SX CMT OR PUMP ENOUGH CMT TO COVER PERFS. PLUG AT 800' WITH 400# HULLS - 15 SX GEL - 50 SX CMT. PLUG AT 350' WITH 80 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/06/2006 10:45 AM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 750' WITH 400# HULLS - 15 SX GEL - 50 SX CMT. 2ND PLUG AT 350' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
5147	5220		
5044	5047		
4958	4964		
4768	4770		

RECEIVED
MAR 13 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Eric MacLaren

(TECHNICIAN)

INVOICED
DATE 3-13-06
INV. NO 2006061266

Form CP-2/3