

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
HUGOTON INFILL

CARD MUST BE SIGNED

Dist. # 1
EFFECTIVE DATE 3-11-06

SGA-YES

Starting Date April 10, 2006
month day year

API Number 15 - 175-22036-00-00

OPERATOR: License # 8061
Name Oil Producers Inc. of Kansas
Address 1710 Waterfront Parkway
City/State/Zip Wichita, KS 67206
Contact Person Lori Wedel
Phone 316-681-0231

IS SECTION REGULAR IRREGULAR
AP. NW. SE. SE. Sec. 7 Twp. 33S S, Rg. 32 W
1250 Ft. from South Line of Section
1250 Ft. from East Line of Section

CONTRACTOR: License # 33375
Name Cheyenne Drilling LP
City/State Garden City, KS
Well Drilled as: X New Recompletion OWWO
Projected Total Depth 2800 feet
Formation Chase Group

NOTE: Attach acreage attribution plat locating both Chase (Hugoton) wells
Total number of acres attributed to unit 621.76
Nearest producing well from same common source of supply 2176 feet
Nearest lease or unit boundary line 1250 feet
County Seward Well # 2A-7
Lease Name Harvey
Ground surface elevation E.S. 2620 feet MSL
Depth to bottom of fresh water 400
Depth to bottom of usable water 460
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1650 feet
Water Source for Drilled Operations:
DWR Permit #: well farm pond X other

If OWWO or Recompletion: old well info as follows:
Operator
Well Name
Comp. Date Old Total Depth


I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 2/20/2006 Signature of Operator or Agent Title Vice President

For KCC Use:
Conductor Pipe Required NONE feet; Minimum Surface Pipe Required 480 feet per Alt. 1 X
This Authorization Expires 9-6-06 Approved By DRW 3-6-06

9/95

Must be filed with K.C.C. five (5) days prior to commencing well
This card void if drilling not started within six (6) months of date received by K.C.C.

A Regular Section of Land
1 Mile = 5,280 Ft.



- Important procedures to follow:
1. Notify District office before setting surface casing.
 2. Set surface casing by circulating cement to the top.
 3. File completion forms ACO-1 with K.C.C. within 120 days of well spud date, following instructions on ACO-1, side 1, and including copies of wireline logs.
 4. Notify District office 48 hours prior to old well workover or re-entry.
 5. Submit plugging report (CP-4) to K.C.C. after plugging is completed.
 6. If an alternate 2 completion, cement in the production pipe from below any useable water to surface within 120 days of spud date.

RECEIVED
FEB 24 2006
KCC WICHITA

State Corporation Commission of Kansas
Conservation Division
130 S. Market Room 2078
Wichita, Kansas 67202-1212
(316) 337-6231

KANSAS

CORPORATION COMMISSION

KATHLEEN SEBELIUS, GOVERNOR
BRIAN J. MOLINE, CHAIR
ROBERT E. KREHBIEL, COMMISSIONER
MICHAEL C. MOFFET, COMMISSIONER

March 2, 2006

Ms. Lori Wedel
Oil Producers Inc. of Kansas
1710 Waterfront Parkway
Wichita, KS 67206

RE: Drilling Pit Application
Harvey Lease Well No. 2A-7
SE/4 Sec. 07-33S-32W
Seward County, Kansas

Dear Ms. Wedel:

District staff has inspected the above referenced location and has determined that the reserve pit shall be constructed **without slots**, the bottom shall be flat and reasonably level, and the free fluids must be removed. The fluids are to be removed from the reserve pit as soon as the Hutchinson Salt section has been drilled through and displacement of the fluids into the reserve pit has occurred. The fluids should be removed again as soon as practical after drilling operations have ceased.


Please keep the pits away from the drainage.

If production casing is set all completion fluids shall be removed from the working pits daily. NO completion fluids or non-exempt wastes shall be placed in the reserve pit.

The fluids should be taken to an authorized disposal well. Please call the District Office at (620) 225-8888 when the fluids have been removed. Please file form CDP-5, Exploration and Production Waste Transfer, within 30 days of fluid removal. Conservation division forms are available through our office and on the KCC web site: www.kcc.state.ks.us/conservation/forms.

A copy of this letter should be posted in the doghouse along with the approved Intent to Drill. If you have any questions or concerns please feel free to contact the undersigned at the above address.

Sincerely,



Kathy Haynes

Environmental Protection and Remediation Department

cc: S Durrant