

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03064-00-01
Spot: SWNENE Sec/Twnshp/Rge: 12-10S-23W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: IRWIN A Well #: 1
County: GRAHAM Total Vertical Depth: 4200 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1960		558 SX CMT
PROD	5.5	4199	0	200 SX CMT # / 36 ⁵⁰
SURF	8.625	190	0	153 SX CMT

Well Type: SWD UIC Docket No: D22420.0 Date/Time to Plug: 03/01/2006 3:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY PIESKER Company: GLM COMPANY Phone: (785) 735-4363

Proposed Plugging Method: Ordered 200 sxs cement and 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2006 4:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV Tool at 1960' w/558 sxs cement.
Tied onto 5 1/2" casing - squeezed with 165 sxs cement with 300# hulls.
Max. P.S.I. 800#. S.I.P. 800#.
Tied onto 8 5/8" x 5 1/2" annulus - pressured to 400# - took no cement.
Total of 165 sxs 60/40 pozmix - 10% gel - 300# hulls.

Perfs:

Top	Bot	Thru	Comments
1538	1592		

Remarks: PFEIFER DOZER SERVICE-WATER.

Plugged through: CSG

District: 04

Signed 110 Roger L Moses

(TECHNICIAN)

RECEIVED

MAR 10 2006

KCC WICHITA

INVOICED

DATE 3-10-06

INV. NO 2006061259

Form CP-2/3

MAR 06 2006

CONTINENTAL OIL

#1 IRWIN 'A'

12-10-23W
SW NE NE

Contr. LOHMANN & JOHNSON

GRAHAM

County

E. 2413 RB Comm. 10-13-55

Comp. 11-18-55

IP 138 BOPD

Tops	Depth	Datum
ANH	1945	468
TOP	3429	-1016
HEEB	3644	-1231
TOR	3679	-1266
KC	3688	-1275
B/KC	3914	-1501
CONG	4090	-1677
ARB	4161	-1748
ID	4200	-1787

Casing
 8" 190
 5" 4199
 DST 3682-3700/1 HR, 30' MUD, BHP 1180#
 DST 4080-4100/2 HR, 90' H OCM, BHP 760#
 DST 4181-4200/1 HR, 2730' SW, BHP 1210#
 CO 4176: 21/4161-68: ACID 500: SQZ: 12/
 4078-82: 42/4086-4100: SWB 8 1/2 BO/12 HR
 NATL: FRAC; SWB 60 BO & 7 BW/10 HR: PB
 3950: 12/3878-82: BAIL 8 GO/2 HR: 12/
 3862-68: BAIL 8 GO/2 HR: 21/3844-51:
 BAIL 8 GO/2 HR: ACID 1000: SQZ: CO 4105
 SWB 48 BO & 4 BW/8 HR:

LAW SE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS