

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-05185-00-00
Spot: SENWSE Sec/Twnshp/Rge: 17-1S-34W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CAHOJ Well #: 45
County: RAWLINS Total Vertical Depth: 4352 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4352	0	w/250 sxs cmt
SURF	8.625	450	0	w/300 sxs cmt

\$ 141.44

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2006 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-1031

Proposed Plugging Method: Ordered 350 sxs Midcon II cement and 1000# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2006 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 450' w/300 sxs cement.
5 1/2" production casing set at 4352' w/250 sxs cement.
PBTB unknown. TD 4352'.
Perforations shut off. LKC zones B,D,G & H with 200 sxs.
Casing hole squeezed from 2492'-2497' w/100 sxs; 2777'-2794' w/200 sxs.
Ran tubing to 2500' - pumped 135 sxs cement with 400# hulls.
Pulled tubing to 1250' - pumped 60 sxs cement with 300# hulls - cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.
Connected to 8 5/8" surface pipe - pumped 25 sxs cement.
Max. P.S.I. 50# S.I.P.0#.

Perfs:

Top	Bot	Thru	Comments
4284	4291		
4245	4248		

Remarks: LEASE FORMERLY KNOWN AS CAHOJ D-2. SWIFT SERVICES, INC. #9668.

Plugged through: TBG

INVOICED

DATE 3-8-06
2006061245

District: 04

100 c

Signed

Darrel Dipman

(TECHNICIAN)

RECEIVED

MAR 08 2006

KCC WICHITA

Form CP-2/3

FEB 27 2006

SKELLY OIL CO

#2 CAHOJ 'D'

17-1-34W
SE NW SE

Contr. C WENTWORTH DRLG

RAWLINS County

E 3163

Comm.

Comp. 11-27-59

IP

440 BOPD

Tops	Depth	Datum
TOP	3854	-691
LANS	4048	-885
B/KC	4314	-1151
MARM	4344	-1181
TD	4352	-1189

Casing
 8" 450
 5" 4352
 DST 4200-12/30", 5' M, P 1255#
 DST 4230-56/1 HR, 1710', 2200'
 O, BHP 1145#
 PERF 4284-87: 4288-91: 80 & 3
 G SW/1 HR: ACID 250: SWP 247 BO,
 NW/4 HR

CAHOJ POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS