

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05099-00-00
Spot: SWNENE Sec/Twnshp/Rge: 27-13S-17W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: ROME Well #: 6
County: ELLIS Total Vertical Depth: 3568 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3557	0	w/unknown sxs cmt
SURF	8.625	120	0	w/unknown sxs cmt

115.96

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2006 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-4459

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing ripped at 1176' and squeezed with 300 sxs cement.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2006 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Hooked up to the annulus and instant 300#.
Swaged onto 5 1/2" - mixed and pumped 300 sxs cement with 500# hulls.
S.I.P. 500#.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer

(TECHNICIAN)
RECEIVED

MAR 08 2006

KCC WICHITA

Form CP-2/3

MAR 06 2006

100

INVOICED
DATE 3-8-06
NO. 2006061245

MURFIN DRILLING

#6

ROME

27-13-17W
SW NE NE

Contr.

ELLIS

County

E 1991 REComm. 8-26-55 Comp. 11-18-55 IP 157 BOPD

PERM PMPG

Tops	Depth	Datum
ANH	1210	+ 781
HEEB	3251	-1260
LANS	3300	-1309
ARB	3535	-1544
TD	3568	-1577

Casing

8" 126

5" 3557

DST 3554-65/1 HR, 120'


V HO & GCM, 150' OIL,

BHP 855#

900' FIH: ACID 1000

4 BOPH/2 HR

SUGARLOAF SE



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS