

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05096-00-00
Spot: NESENE Sec/Twnshp/Rge: 11-12S-18W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: STAAB Well #: 4
County: ELLIS Total Vertical Depth: 3688 feet

Operator License No.: 30553
Op Name: UNREIN, GLENN DBA UNREIN OIL CO
Address: 300 W. 40TH STREET
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3688	0	w/unknown sxs cmt
SURF	8.625	195	0	w/unknown sxs cmt

119.80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2006 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE THOMASON Company: UNREIN, GLENN DBA UNREIN OIL Phone: (785) 628-6231

Proposed Plugging Method:
02/27/2006 - Ordered 525 sxs 60/40 pozmix - 10% gel - 1100# hulls.
02/28/2006 - Ordered 400 sxs 60/40 pozmix - 10% gel - 1000# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2006 5:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

ELI shot a two hole perf at 775' and 1400'.
Professional Well Service RIH with tubing to 2375'.
Allied rigged to tubing and pumped 100 sxs 60/40 pozmix with 300# hulls mixed in - no returns.
Pulled tubing to 1450'. Allied rigged to tubing and pumped 100 sxs 60/40 pozmix with 200# hulls mixed in - no returns.
Pulled tubing to 950'. Allied rigged to tubing and pumped 125 sxs 60/40 pozmix - no returns.
RIH to 2013'. Rigged up and pumped 50 sxs cement with 200# hulls mixed in.
Pulled tubing to 1400' and pumped 150 sxs cement with 400# hulls mixed in - no returns.
02/28/2006 - Rigged to 5 1/2" casing and pumped 60 sxs cement with 200# hulls mixed in.
Max. P.S.I. 700#. S.I.P. 500#.
Backside pressured to 500# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3660	3665		
3650	3653		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

INVOICED
DATE 3-8-06
NO. 2006061249

100

Signed [Signature]
(TECHNICIAN)

District: 04

MAR 01 2006

RECEIVED
MAR 08 2006
KCC WICHITA

WICK PETROLEUM

#4

STAAB

11-12-18w
NE SE NE

Contr. WICK PET

ELLIS County

E 2114^{RB} Comm. 3-17-55 Comp. 5-13-55 IP 45 BOPD

Tops	Depth	Datum
1382		+732
TOP	3088	-974
HEEB	3323	-1209
LANS	3369	-1255
SIMP	3611	-1497
ARB	3636	-1522
TD	3688	-1574

Casing

8" 195

5" 3688

DST 3286-96/1/2 HR, 20' MUD

DST 3430-70/1 HR, 20' OIL

SPTD MUD:

PERF 3660-65: ACID 500: PB

3657: PERF 3650-53: ACID

500'

WALTERS POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS