

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04931-00-00
Spot: SESWNW Sec/Twnshp/Rge: 24-20S-12W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SCHEUFLER Well #: 1
County: BARTON Total Vertical Depth: 3362 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3337	0	150 SX CMT
SURF	8.625	224	0	150 SX CMT

\$ 109.27

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2006 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 10% gel - 400# hulls.
Sanded off bottom to 3009' and topped with 5 sxs cement.
Tied onto casing and casing parted at 570'.
RIH with tubing to 600' and stacked out on busted casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2006 10:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 600'. Allied rigged to tubing and pumped 40 sxs 60/40 pozmix neat, followed with 155 sxs with 400# hulls mixed in to circulate cement into pit. Pulled tubing. Tied onto 8 5/8" casing with a swedge and pumped 25 sxs 60/40 pozmix. Max. P.S.I. 500#. S.I.P. 450#.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #23636.

Plugged through: TBG

INVOICED

DATE: 3-8-06
2006061250

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

Form CP-2/3

MAR 08 2006

KCC WICHITA

MAR 02 2006

GRAHAM-MESSMAN-RINEHART

#1

SCHUEFLER

24-20-12W 53
SE SW NW

Contr.

BARTON

County

E 1809

Comm.

Comp.

10-27-50

IP

248 BOPD

PHY POT

Tops	Depth	Datum
HEEB	2965	-1156
BR LM	3091	-1282
LANS	3118	-1309
CONG	3326	-1517
ARB	3336	-1527
T.D.	3362	-1553

Casing

8" 224

5" 3337

ACID 1500: PMP
56 80/12 HRS

BRYANT POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS