

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21377-00-00
Spot: NWSESW Sec/Twnshp/Rge: 3-11S-22W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: FLAX B Well #: 2
County: TREGO Total Vertical Depth: 3953 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3942	0	w/150 sxs cmt
SURF	8.625	302	0	w/175 sxs cmt

128 47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2006 8:30 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: Ordered 200 sxs cement.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2006 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

P.C. at 1702' w/unknown amount of cement.
Squeezed at 1850' w/300 sxs cement.
01/04/2006 - Cemented 2 3/8" tubing into 5 1/2" casing with 100 sxs cement.
02/01/2006 - Ran in hole with 2" bit to drill out cement - got stuck with bit at 1250'.
Could not pull tubing and bit - shot bit off - pulled one joint of 1" and circulated with 15 sxs cement.
Pulled all tubing and circulated 125 sxs cement thru 2 3/8" out thru 5 1/2" casing (when shooting off bit, must have punctured hole thru 2 3/8" tubing).
Tied to 8 5/8" x 5 1/2" annulus to squeeze - squeezed 10 sxs into annulus at 500# and blew a hole in surface pipe below braden head.
Total of 150 sxs 60/40 pozmix - 10% gel.

Perfs:

Remarks: COPELAND ACID CEMENTING. ATS-WATER.

Plugged through: TBG

District: 04

RD

Signed Roger L. Moses
(TECHNICIAN)

MAR 06 2006

RECEIVED
MAR 10 2006
KCC WICHITA

INVOICED
3-10-06
2006061258

REPLACEMENT CARD

TRIPLE H OIL OPERATIONS
BOX 248
HAYS, KS 67601


#2 "B" FLAX

3-11-22W
NW SE SW

CONTR DREILING OIL, INC. CTY TREGO

GEOLOGICAL DEMURRY

ELV 2215 KB SPD 11/10/83 CARD ISSUED 1/12/84 # OIL WELL
2210 GL MARM 3810-3840



LOG	Top	Depth/Datum
ANH	1686 +	529
B/ANH	1729 +	486
HEEB	3459-	1244
TOR	3482-	1267
LANS	3498-	1283
STARK SH	3690-	1475
BKC	3735-	1520
MARM	3807-	1592
ARB	3921-	1706
RTD	3950-	1735
LTD	3953-	1738

API 15-195-21,377
8 5/8 " 302 / 175SX; 5 1/2 " 3942 / 150SX; PORT COLLAR AT 1702
DST (1) 3809-3840 (MARM) / TIMES NA, 248' GIP, REC 370'
FREE OIL, PRESSURES NA
MICT - CO, PF (MARM) 3810-40, W/1 SPF, AC 3600G (15%) & 1000 BBLs FRESH WTR FLUSH, SWB LD, SO, SET 2 3/8 " TBG AT 3888', POP

INFO RELEASED: 5/31/84 - WAS OIL WELL - TIGHT HOLE
NOTE: INFO RELEASED 1/26/84 - ADDED WELL INFO

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

WICHITA