

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21726-00-00
Spot: NWSENE Sec/Twnshp/Rge: 14-9S-24W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: NICKELSON A Well #: 3
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4039	0	200 SX CMT
SURF	8.625	200	0	125 SX CMT

\$131 ³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2006 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY PIESKER Company: GLM COMPANY Phone: (785) 735-4363

Proposed Plugging Method: Ordered 290 sxs cement - 16 sxs gel - 600# hulls.
Perforate at 2200' and 1025'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2006 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2000' - spotted 70 sxs cement and 300# hulls.
Pulled tubing to 1080' - circulated with 90 sxs cement.
Pulled all tubing and topped well off with 20 sxs cement.
Tied to annulus - squeezed with 75 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.
Total of 255 sxs 60/40 pozmix - 10% gel - 300# hulls.

Perfs:

Top	Bot	Thru	Comments
3986	3992		
3962	3966		

Remarks: PFEIFER DOZER SERVICE-WATER.

Plugged through: TBG

District: 04

Signed 1/100 Roger Moses

(TECHNICIAN)

RECEIVED

MAR 10 2006

KCC WICHITA

INVOICED

DATE 3-10-06

2006061259

Form CP-2/3

MAR 06 2006

11/10/83
414

RUSSELL O. NICKELSON #3 "A" NICKELSON 14-9-24W
 ROUTE 1, BOX 109 PENOKEE, KS 67659 NW SE NE
 CONTR SANTA FE DRILLING CTY GRAHAM
 GEOL _____ FIELD HOLLEY SE
 ELY NA SPD E 12/15/82 CARD ISSUED 7/7/83 # OIL WELL
 LKC - INTV NA

+	+	+
+	+	+
+	+	+

API 15-065-21,726

Tops	Depth/Datum
NO TOPS AVAILABLE	
ERTD	4040

E 8 5/8 " 200; PROD CSG NA
 MICT - CO, PF (LKC) INTV NA, SWB DWN, SO, POP TIGHT HOLE
 - NO OTHER INFO TO BE RELEASED AT PRESENT - WILL RE-
 LEASE INFO WHEN AVAILABLE - TEMP COMP - 7/7/83

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS