

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21143-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 14-9S-24W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: NICKELSON A Well #: 1
County: GRAHAM Total Vertical Depth: 4030 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4029	0	200 SX CMT
SURF	8.625	206	0	125 SX CMT

130⁹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2006 1:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY W. PIESKER Company: GLM COMPANY Phone: (785) 735-4363

Proposed Plugging Method: Ordered 300 sxs cement - 600# hulls - 16 sxs gel.
Perforate at 1025' and 2200'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2006 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Tied to 5 1/2" casing - spotted 40 sxs cement with 300# hulls, followed with 16 sxs gel.
Squeezed casing with 240 sxs cement.
Max. P.S.I. 400#. S.I.P. 100#.
Tied to 8 5/8" x 5 1/2" annulus - squeezed 75 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.
Total of 355 sxs 60/40 pozmix - 10% gel - 16 sxs gel - 300# hulls.

Perfs:

Top	Bot	Thru	Comments
3970	3976		

Remarks: PFEIFER DOZER SERVICE-WATER.

Plugged through: CSG

District: 04

Signed _____

Roger L. Moses
(TECHNICIAN)

RECEIVED

MAR 10 2006

KCC WICHITA

INVOICED

DATE 3-10-06

INV. NO. 2006061259

Form CP-2/3

MAR 06 2006

R. L. NICKELSON PETROLEUM EXPLORATIONS 14-9-24W
 ROUTE #2 #1A NICKELSON SE NW NE
 EL DORADO, KS. 67042
 CONTR RED TIGER DRILG. CO. CTV GRAHAM

GEOL _____ FIELD HOLLEY SE
 E 2480 KB CM 7/2/79 CARD ISSUED 8/25/79 IP P 90 BOPD, NW
 LKC 3970-76

+	+	+
+	+	+
+	+	+

API 15-065-21,143

LOG	TOPS	DEPTH	DATUM
SC		2125	+ 355
HEEB		3780	-1300
TOR		3802	-1322
LKC		3816	-1336
BKC		4025	-1545
RTD		4030	-1550

8-5/8" 206, 5 1/2" 4029/200sx
 DST (1) 3840-3910 (LKC)/30-30-30-30,
 175' HOCM, SIP 920-899#, FP 71-
 112/112-132#
 DST (2) 3965-92 (LKC)/30-30-30-30,
 1970' GIP, REC 630' o, 180' MCO,
 NW, SIP 1125-1115#, FP 81-193/153-
 155#
 DST (3) 4000-15 (LKC)/30-30-30-30, 15'
 M, SIP 1053-648#, FP 51-61/51-51#
 MICT - CO, PF (LKC) 3970-76, AC 250,
 SWB 10 BOPD NW BOP