

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-01672-00-01  
Spot: NENWNE Sec/Twnshp/Rge: 25-15S-14W  
4950 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: BOOMHOWER OWWO Well #: 1  
County: RUSSELL Total Vertical Depth: 3326 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3321	0	w/unknown sxs cmt
SURF	10.75	377	0	w/unknown sxs cmt

\$ 108.10

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/21/2006 1:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/21/2006 5:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 1300' - pumped 100 sxs 60/40 ozmix - 10% gel cement.  
Pulled to 650' - pumped 150 sxs cement.  
Pulled to 325' - pumped 200 sxs cement.  
POOH. Filled casing with 75 sxs cement. Stayed full.  
Backside full of cement.

Remarks: COPELAND CEMENTING.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

**INVOICE**  
DATE 3-8-06  
INV. NO. 2006061237

MAR 02 2006

RECEIVED  
MAR 08 2006  
KCC WICHITA

CRUDE PRODUCERS, INC.

BOX 55

RUSSELL, KS 67665

#1 BOOMHOWER "OWWO"

25-15-14W  
NE NW NE

CONTR ZIGLER WELL SERV., INC. CTY RUSSELL

GEOL \_\_\_\_\_ FIELD TRAPP

E 1893 CM 9/1/79 CARD ISSUED 2/28/80 IF P 10 80 & 700 BWPD  
ARB OH 3318-26

+	+	+
+	+	+
+	+	+

API NOT ASSIGNED

TOPS	DEPTH	DATUM
ARB	3322	-1429
TD	3326	-1433
Awh	874	+1017

OLD INFO: OPERATOR WAS CITIES SERVICE  
OIL CO., #8 BOOMHOWER, SPD 7/28/37,  
SET 10" 377, 7" 3321, COMPLETED AS  
2377 BOPD 8/17/37  
A/2000

NEW INFO: RE-ENTERED 9/1/79, WSH  
OWN TO 3326, SET 7" 3318, MICT - CO,  
(ARB OH), TST GSO & WTR, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

ORIGINAL