

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21671-00-00
Spot: SESENW Sec/Twnshp/Rge: 34-12S-17W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SCHMIDT Well #: 1
County: ELLIS Total Vertical Depth: 3608 feet

Operator License No.: 32875
Op Name: CWB - CO, A GENERAL PARTNERSHIP
Address: 40837 BEAR CREEK ROAD
SPRINGVILLE, CA 93265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3595	0	w/100 sxs cmt
SURF	8.625	193	0	w/125 sxs cmt

\$117.26

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2006 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JAMES HERTEL Company: CWB COMPANY Phone: (785) 650-3118

Proposed Plugging Method: Ordered out 100 sxs 60/40 pozmix - 10% gel - 200# hulls.
TOF at 1439'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2006 6:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 250' - 750' and 1300'.
TIH with tubing to 1400' - circulated cement with 100 sxs cement. POOH.
Field agent ordered 200 more sacks 60/40 pozmix - 10% gel.
Swaged onto 4 1/2" and pumped 100 sxs cement with 200# hulls -
cement circulated up 8 5/8" - shut in.
Squeezed well with 25 sxs cement.
S.I.P. 500#.


Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 3-8-06

MAR 06 2006 2006061238

RECEIVED

MAR 08 2006

KCC WICHITA

N - B COMPANY, INC.

BOX 506

RUSSELL, KS 67665

#1 SCHMIDT

34-12-17W
SE SE NW

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOL FRANCIS WHISLER FIELD SCHMEIDLER S E

E 2047 KB 4/24/79 CARD ISSUED 7/28/79 IP P 45 BOPD & WTR
LKC 3330-89 OA

+	+	+
.	.	.
+	+	+

API 15-051-21,671

SMP	TOPS	DEPTH	DATUM
ANH		1235	+ 812
TOP		3016	- 969
HEEB		3257	-1210
TOR		3277	-1230
LANS		3304	-1257
BKC		3540	-1493
ARB		3592	-1545
RTD		3608	-1561

8-5/8" 193/125sx, 4 1/2" 3595/100sx

NO LOG

DST (1) 3293-3393/15-60-45-60, 620'
MGO, SIP 969-928#, FP 102-183/
224-285#

DST (2) 3454-96/15-30, 10'M, ISIP 51#,
IFP 30-30#

MICT - CO, PF (LKC) 12/3386-89, AC 500,
SWB 3.75 BFPH, 65% O/4HRS, SWB 5 1/2
BFPH, 65% O/3 HRS, AC 1500, SWB 7 1/2
BFPH, 65% O/4HRS, PF (LKC) 3330-34, AC
1500, SWB 3 1/2 BFPH, 80% O, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INDEX