

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22700-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 1-18S-12W
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: DREWS Well #: 1
County: BARTON Total Vertical Depth: 3440 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3435	2408	
PROD	5.5	3435	0	150 SX CMT
SURF	8.625	624	0	325 SX CMT

\$111.80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/13/2006 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: GLOBE OPERATING, INC. Phone: (620) 792-7607

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2006 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3220' and dumped 5 sxs cement.
Cut off casing at 2400'.
Pulled to 1525' - pumped 105 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 775' - pumped 40 sxs cement with 100# hulls.
Pulled to 250' and circulated with 60 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3422	3426		
3281	3285		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 3-8-06

MAR 02 2006 INV. NO. 2006061242

RECEIVED
MAR 08 2006
KCC WICHITA

PETROMARK EXPLORATION, INC.

7030 S. YALE, #711


#1 DREWS

1-18-12W
NW SW NW

TULSA, OK 74136

CONTR MUSTANG DRLG. & EXPL., INC. CTY BARTON

GEOL _____ FIELD KINZEL EXT(1/8 E)



ELV 1878 KB SPD 4/28/82 CARD ISSUED 3/24/83 IP OIL WELL
1873 GL ARB OH 3435-3443

API 15-009-22,700

LOG	Tops	Depth/Datum	
HEEB	3022-1144	8 5/8 " 624/325SX; 5 1/2 " 3435/150SX
TOR	3042-1164	DST (1) 3151-81 (LKC) / MISRUN
DOUG	3054-1176	DST (2) 3151-84 (LKC) / OP 120", REC 60' OIL SPKD M, SIP 107-83#, FP 35-35 / 35-35#, HP 1614-1602#
BR LM	3127-1249	DST (3) 3224-84 (LKC) / TIMES NA, REC 360' MW, W / FEW OIL SPKS, SIP 1033-997#, FP 59-95 / 142-166#, HP 614-602#
LANS	3140-1262	DST (4) 3271-90 (LKC) / TIMES NA, REC 30' M, PRESSURES NA
BKC	3390-1512	DST (5) 3404-21 (PENN, ARB) / TIMES NA, REC 90' M, SIP 760-665#, FP 83-59 / 59-59#, HP 760-1721#
ARB	3414-1536	DST (6) 3421-43 (ARB) / 45-45-45-45, REC 720' CL GSY OIL, 230' SMO, SIP 1021-962#, FP 119-202 / 250-321#, HP 1804-1792#, BHT 115°
LTD	3440-1562	MICT - CO (ARB OH 3435-43), SWB DWN, W / GSO, NAT, SWB 3.48 BF, 80% OIL, POP, 7/1/82
RTD	3443-1565	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS