

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20450-00-00
Spot: W2W2 Sec/Twnshp/Rge: 28-4S-22W
2540 feet from N Section Line, 730 feet from W Section Line
Lease Name: FIN BELDEN Well #: 1
County: NORTON Total Vertical Depth: 3775 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		

\$ 122⁶⁹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/03/2006 6:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 03/03/2006 9:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3700' w/25 sxs.
2nd. Plug at 1975' w/25 sxs.
3rd. Plug at 1175' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

RECEIVED
MAR 09 2006
KCC WICHITA

INVOICED

DATE 3-9-06
2006061254

MAR 08 2006