

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20419-00-00
Spot: W2SESESW Sec/Twnshp/Rge: 26-16S-11E
360 feet from S Section Line, 2140 feet from W Section Line
Lease Name: WHEAT Well #: D2-26
County: LYON Total Vertical Depth: 2430 feet

Operator License No.: 33240
Op Name: WOLVERINE ENVIRONMENTAL PROD
Address: ONE RIVERFRONT PLAZA 55 CAMPA
GRAND RAPIDS, MI 49503

PROD Size: 5.5 feet: 2430 185 SX CMT
SURF Size: 8.625 feet: 201 98 SX CMT

78⁹⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/08/2004 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: EXACT ENGINEERING, INC Company: _____ Phone: (918) 599-9400

Proposed Plugging Method: SET 50' ABOVE TOP PERFORATION, SET 50' PLUG ABOVE THE LOCATION WHERE WE SHOOT OFF THE CASING, SET A 350' PLUG FROM 350' TO SURFACE. CUT OFF CASING BELOW PLOW DEPTH AND RETURN LAND TO NATURAL STATE AS NEAR AS POSSIBLE.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE
Date/Time Plugging Completed: 05/08/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

PUMPED GEL INTO WELL TOP TO BOTTOM, PUMPED 50' CEMENT PLUG @ 2223' THRU TUBING, PULLED TUBING OUT, SHOT CASING @ 567' PUMPED 50 CEMENT PLUG, PULLED CASING TO 350' PUMPED 350' CEMENT PLUG.

Perfs:

Top	Bot	Thru	Comments
2297	2298		
2277	2278		
2254	2255		
2227	2228		

RECEIVED
KCC DISTRICT #3

AUG 16 2004 *mh*

CHANUTE, KS

RECEIVED
AUG 24 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

INVOICED

DATE

8-24-04

APP. NO.

2005060396