

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22311-00-00
Spot: SWNWSWSE Sec/Twnshp/Rge: 23-14S-21W
920 feet from S Section Line, 2530 feet from E Section Line
Lease Name: DINKLE Well #: 1-23
County: TREGO Total Vertical Depth: 4100 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

\$ 133.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/23/2005 4:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DOWNING-NELSON OIL COMPAN Phone: (785) 628-3449

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: JAY PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 11/23/2005 5:15 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

1st. Plug at 1590' w/25 sxs.
2nd. Plug at 925' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.


Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

RECEIVED

MAR 08 2006

KCC WICHITA

Form CP-2/3

INVOICED

DATE

3-8-06

INV. NO.

200606240

MAR 06 2006