

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-055-10158-00-00  
 Spot: SESWNE Sec/Twnshp/Rge: 27-21S-34W  
2310 feet from N Section Line, 1650 feet from E Section Line  
 Lease Name: NUNN Well #: 3  
 County: FINNEY Total Vertical Depth: 4707 feet

Operator License No.: 30535  
 Op Name: HARTMAN OIL CO., INC.  
 Address: 12950 E. 13TH  
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1200		WITH 2 SX CMT
CIBP		2305		WITH 2 SX CMT
CIBP		4310		
PROD	5.5	4610	0	WITH 300 SX CMT
SURF	10.75	286		WITH 400 SX CMT

\$ 152.98

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
 Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
 Proposal Rcvd. from: STAN MITCHELL Company: \_\_\_\_\_ Phone: (620) 277-2511

Proposed Plugging Method: AS PER KCC - RICHARD LACEY - (2-15-2006) SET CIBP @ 2316' - SET 2nd CIBP @ 1200' - PERFORATE 5-1/2" CSG. 2 HOLES @ 1100' - (2-21-2006) WILL RUN TBG. SPOT 100 SX CLASS A COMMON CMT W/3% CC @ 1100' SPOT 50 SX 60-40 W/6% GEL @ 300'. (CIRCULATE CEMENT TO SURFACE) - PUMP 250 SX 60/40 W/6% GEL DOWN 10-3/4".

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 02/21/2006 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF FISH @ 3251'. COULD NOT GET BELOW 2460' WITH BIT. 1ST PLUG CIBP @ 2305' WITH 2 SX CMT. 2ND PLUG CIBP @ 1200' WITH 2 SX CMT. 3RD PLUG PERFORATE @ 1100'. RUN TUBING TO 1100' & PUMP 100 SX CMT W/100# HULLS. WAIT ON CMT 2 HOURS. TAG @ 297'. FILL CASING WITH 35 SX CMT. 4TH PLUG PUMP 265 SX CMT DOWN 10 3/4" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 200#. SHUT IN PRESSURE 100#.


Perfs:

Top	Bot	Thru	Comments
4610	4707		
4282	4298		

Remarks: USED CLASS A CMT & 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Ken Jehlik

(TECHNICIAN) RECEIVED

MAR 08 2006

KCC WICHITA

Form 01/3

INVOICED

DATE 3-8-06  
 INV. NO. 2006061245