

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19046-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 23-19S-12W  
4290 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: LANTERMAN A Well #: 5  
County: BARTON Total Vertical Depth: 3404 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: P.O. BOX 1469  
PLAINFIELD, IL 60544

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3404	0	150 SX CMT
SURF	8.625	252	0	130 SX CMT

63  
\$ 110

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2006 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: RUSSELL OIL, INC. Phone: (815) 609-7000

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2006 12:30 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Tried to drill out with power swivel. Got to 713' - drilling on metal.  
Ran tubing to 650'.  
Circulated with 105 sxs 60/40 pozmix - 10% gel cement.  
POOH. Tied onto casing and circulated backside with 65 sxs cement - shut in.  
Pumped 180 sxs cement down casing.  
Max. P.S.I. 700#. S.I.P. 250#.

**Perfs:**

Top	Bot	Thru	Comments
3342	3348		
3312	3316		
3282	3290		
3162	3170		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED  
DATE 3-8-06  
INSTR. NO. 2006061248

District: 04

100

Signed Case Morris  
(TECHNICIAN)

RECEIVED  
MAR 08 2006  
KCC WICHITA

Form CP-2/3

MAR 02 2006