

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
MAR 10 2006
KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Unrein Oil Co.
Address: 300 W. 40th St. Hays, Kansas 67601
Phone: (785) 628-6231 Operator License #: 30553
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/24/2006 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arb. _____ Depth to Top: 3650 Bottom: 3665 T.D. 3688
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-05096-00-00
Lease Name: Staab
Well Number: 4
Spot Location (QQQQ): _____ - NE - SE - NE
3630 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 11 Twp. 12 S. R. 18 East West
County: Ellis
Date Well Completed: 5/13/55
Plugging Commenced: 2/24/06
Plugging Completed: 2/28/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Top	lime, shale	3088	3323	8 5/8"	195	none
L/KC	lime, shale	3369	3611	5 1/2"	3687	none
Arb	dol.	3636	3688			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

ELI wireline shot 2 holes at 775' and 2 holes at 1400', Professional well service RIH with tubing to 2357', Allied Cementing pumped 100 sx 60/40 posmx down tubing with 300# hulls, pulled tubing to 1400' pumped 100sx of same with 200# hulls mixed in. pulled tubing to 950' pumped 125sx of same, did not circulate. RIH to 2013' pumped 50 sx with 200# hulls, pulled tubing to 1400' pumped 150 sx with 400# hulls, left set over nite, pumped 60sx down casing with 200# hulls, max SIP. 700# . Back side SIP500#

Name of Plugging Contractor: Allied Cementing Co. Professional Pulling Service License #: None 32810
Address: Box 31, Russell, Kansas 67665
Name of Party Responsible for Plugging Fees: Unrein Oil Co.
State of Kansas County, Ellis, ss.
Glenn Unrein (Employee of Operator) or (Operator) on above-described well, being first duly

KCC
BEM
3-15-06
RBDMS
CP 2/3

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the

same are true and correct, so help me God
NOTARY PUBLIC - State of Kansas
STEVEN THOMASON
My Appt. Expires 9/3/09

(Signature) [Signature]
(Address) 300 W. 40th, Hays, Kansas 67601

NOTARY PUBLIC - State of Kansas
STEVEN THOMASON
My Appt. Expires 9/3/09

SUBSCRIBED and SWORN TO before me this 1 day of March, 20 06
[Signature] My Commission Expires: 9/3/09
Notary Public

BW