

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: A G V Corp.

Address: 123 N Main Attica, KS 67009

Phone: (620) 254-7222 Operator License #: 5039

Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 3-1-2006 (Date)

by: Steve Van Gieson (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (if needed attach another sheet)

Stalnaker Depth to Top: 3000 Bottom: 3087 T.D. 3087

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-191-22394-0000

Lease Name: Haskins

Well Number: A1

Spot Location (QQQQ): 150' N C SW NE

1830 Feet from  North /  South Section Line

1980 Feet from  East /  West Section Line

Sec. 26 Twp. 32 S. R. 4  East  West

County: Sumner

Date Well Completed: 7-15-2003

Plugging Commenced: 3-6-2006

Plugging Completed: 3-8-2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface				8 5/8	267'	None
Production				5 1/2	3083'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 2950', dump baler ran 2 SX cement on plug, ran free point log casing stuck at 320', perforate 650' squeeze 35 SX cement, perforate 285' squeeze 115 SX cement, ran 175' 1" in annulus and pump 75 SX cement, top out casing with 15 SX cement, circulate cement to surface.

Name of Plugging Contractor: Basye Well Service Inc. License #: 33204

Address: 517 S Main Stafford, Ks 67578

Name of Party Responsible for Plugging Fees: A G V Corp. 123 N Main Attica, Ks 67009

State of Kansas County, Harper, ss.

Larry G Mans (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry G Mans


(Address) 123 N Main Attica Ks 67009

SUBSCRIBED and SWORN TO before me this 13 day of March, 20 06

Kayla Tompkins My Commission Expires: 4-24-2007  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
MAR 14 2006  
KCC WICHITA



*bm*