



15-065-20222-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Incorporated,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Legere Well No. 1

Location: NE-NW-SE Sec. 25 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 3745' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Barnes was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3735'--5 1/2" Production casing cemented on bottom with 100 Sx. Well  
plugged back to 3741'.

Sand well back to 3700' and set 5 Sx. cement with dump bailer. Pull 5 1/2"  
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 130 Sx.  
cement. staged.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

7-23-69  
N. L. Nichols  
Conservation Division Agent