



15-069-20291-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
12-24-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Helberg of Helberg Oil Company has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Delbert Worcester,

Complete Address: Hill City, Kansas.

Lease Name: Worcester Well No. 3

Location: SW-NE-NW Sec. 23 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 3800' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

249'--8 5/8" Surface casing, cement circulated with 135 Sx.  
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 900' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.  
Pull DP, set plug @ 40' with 1/2 sack cement and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent