



15-163-20894-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Strecker of Abercrombie Drlg. has this date requested permission to plug the following described well:

Mr. Strecker guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg., Inc.

Complete Address: 801 Union Ctr. Wichita, Ks.

Lease Name: Graham Well No. 1

Location: NW SW SW Sec. 10 Twp. 7 Rge. (E)(W) 19

County: Rooks Total Depth 3490' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Strecker was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill

pipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR - 1 1979

Very truly yours CONSERVATION DIVISION
Wichita, Kansas

3-1-79

Red Massey
Conservation Division Agent